GENERAL: THE A.I.A. "GENERAL CONDITIONS OF THE CONTRACT" ARE HEREBY INCORPORATED AS IF COMPLETELY REPRODUCED HEREIN, EXCEPT AS SPECIFICALLY MODIFIED WITHIN THESE SHORT THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXISTING CONDITIONS PRIOR TO BIDDING AND SHALL VISIT SITE AND BECOME FAMILIAR AS TO THE CONDITION OF THE PREMISES AND THE EXTENT AND CHARACTER OF THE WORK TO BE DONE. ALL WORK SHALL CONFORM WITH THE REQUIREMENTS OF THE MOST CURRENT LEGAL GOVERNING BUILDING CODE, LOCAL CODES, NATIONAL ELECTRIC CODE, N.F.P.A. RECOMMENDATIONS, OSHA, AND ALL OTHER APPLICABLE CODES, RULES AND REGULATIONS ALL IN THEIR LATEST LEGAL EDITION OF THE AUTHORITY HAVING JURISDICTION OVER WORK OF THIS TYPE. ALL WORK THAT IS EITHER IMPLIED OR REASONABLY INFERABLE FROM THE CONTRACT DOCUMENTS, DRAWINGS, AND SPECIFICATIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ALL DRAWINGS ARE DIRECTED TO THE ATTENTION OF THE CONTRACTOR AND THE INCLUSION OF ANY WORK BE IT MENTION, NOTE, DETAIL ITEMIZATION OR IMPLICATION HOWEVER BRIEF, MEANS THAT THE CONTRACTOR SHALL PROVIDE AND INSTALL SAME. ALL WORK PERFORMED SHALL INCLUDE ALL APPARATUSES AND APPARATUS NORMALLY DEEMED TO BE PART OF A COMPLETE PACKAGE WITHIN THE DEFINITIONS OF A NORMAL INDUSTRY STANDARDS. EACH SUB-TRADE SHALL BE RESPONSIBLE FOR REVIEWING AN ENTIRE SET OF DRAWINGS AND NORMAL MODEL AND CORPORATION OF A NORMAL INDUSTRY STANDARDS. NOTING WORK APPLICABLE AND COORDINATING HIS WORK WITH THE WORK OF ALL OTHER ALL PERMITS, INSPECTIONS, APPROVALS, ETC. SHALL BE APPLIED FOR AND PAID BY EACH CONTRACTOR IN ALL FIELDS OF HIS WORK AND HE SHALL BE RESPONSIBLE FOR THE COORDINATION OF INSPECTIONS AND APPROVALS OF HIS WORK. ALL WORK COMPLETED OR OTHERWISE SHALL BE PROPERLY PROTECTED AT ALL TIMES. THE CONTRACTOR SHALL FOLLOW ALL ACCEPTED METHODS OF SAFETY PRACTICE AND PROVIDE ALL FENCE BARRICADES, ETC. AS MAY BE NEEDED TO PROTECT LIFE AND PROPERTY AS MAY BE REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER THAT TYPE WORK. THE GENERAL CONTRACTORS, SHALL REPAIR (AT HIS OWN COST) ANY DAMAGES TO THE PREMISES OR ADJACENT WORK CAUSED BY HIS OPERATION. EACH CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE PROJECT THROUGH INSPECTION OF THE SITE, THE DRAWINGS AND SPECIFICATIONS, SO AS TO THOROUGHLY UNDERSTAND THE WORK ANY AND ALL DISCREPANCIES AND OMISSION SHALL BE REPORTED TO THE ARCHITECT PRIOR TO COMMENCEMENT OF ANY WORK FOR IMMEDIATE RESOLUTION. ANY WORK THAT PROCEEDS OTHERWISE (IF INCORRECTLY PERFORMED) SHALL BE REPLACED OR REPAIRED WITH THE COST FOR SAME BEING HONORED BY THE GENERAL CONTRACTOR. THE CONTRACTOR SHALL FURTHER VERIFY ALL DIMENSIONS FOR COORDINATION WITH ALL OTHER TRADES. COMMENCEMENT OF CONSTRUCTION SHALL BE DEEMED AS ACCEPTANCE OF ALL EXISTING CONDITIONS AND BECOME THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. THE FRAMING CONTRACTOR SHALL PROVIDE PROPERLY SIZED CHASES. HOLES OR OPENINGS FOR HIS WORK AND THE WORK OF HIS SUBCONTRACTORS CUTTING INTO EXISTING WORK AS MAY BE NECESSARY FOR PROPER INSTALLATION OF HIS OWN OR OTHER CONTRACTORS WORK SHALL BE NECESSARY FOR PROPER INSTALLATION OF HIS OWN OR OTHER CONTRACTORS WORK SHALL BE REPAIRED AND REINFORCED TO MAINTAIN STRUCTURAL INTEGRITY IN CASE OF HIS FAILING TO COORDINATE AND OR PROVIDE SUCH OPENING SHALL THEN BE PROVIDED AFTERWARDS AT HIS OWN EXPENSE. NO EXCESSIVE CUTTING WILL BE PERMITTED NOR SHALL ANY STRUCTURAL MEMBERS BE CUT WITHOUT THE WRITTEN AUTHORIZATION OF THE ARCHITECT. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR THE COORDINATION OF ALL WORK. ANY AND ALL OPENINGS IN FIRE RATED WALLS CREATED OR DISCOVERED BY THE CONTRACTOR SHALL BE REPAIRED AND FILLED WITH ARCHITECT APPROVED FIRE SAFETY MATERIALS.

9. ALL CONTRACTORS WORK SHALL BE PERFORMED IN A PROFESSIONAL, CLEAN AND ACCURATE MANNER. CONTRACTOR SHALL CLEAN ALL NEW AND EXISTING SURFACES SO AS TO BE FREE OF ALL DIRT AND WEAR CAUSED BE DEBRIS FROM ALL INSTALLATIONS OF OTHER TRADES. CONTRACTOR SHALL PROPERLY PROTECT ALL ADJACENT SURFACES DURING THE COURSE OF HIS

O. THE OWNER RESERVES THE RIGHT TO MAKE CHANGES IN THE DRAWINGS AND SPECIFICATIONS AS THE WORK PROGRESSES. BULLETINS, CHANGE ORDERS, DRAWINGS SPECIFICATIONS OR INSTRUCTIONS COVERING SUCH CHANGES WILL BE ISSUED TO THE CONTRACTOR, IT IS THE

RESTRUCTIONS COVERNING SIGN CHANGES WILL STRIBUTE THESE CHANGES IMMEDIATELY BY REPORTING ALL SUBCONTRACTORS AND LOCAL OFFICIALS AFFECTED TO TAKE SUCH MEASURE AS MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE WORK WHICH MAY DUE TO THE WORK WHICH WHICH WHICH WAS DUE TO THE WORK WHICH WHICH WAS DUE TO THE WORK WHICH WHICH

MAY BE NECESSARY TO AVOID ERRORS IN THE WORK WHICH MAY OCCUR DUE TO THE USE OF A SUPERSEDED DRAWINGS' WORK AFFECTED BY CHANGES PROPOSED IN ANY REVISED DRAWINGS OR OTHER DOCUMENTS ISSUED BY THE CONTRACTOR. THE WORK CHANGES SHALL FURTHERMORE NOT BE PROCEEDED UNLESS THE AFOREMENTIONED CHANGES ARE ACCOMPANIED BY LETTER OR AUTHORIZATION FROM THE ARCHITECT AUTHORIZING THE CONTRACTOR TO PROCEED WITH THE CHANGES. ACCORDINGLY, IN ANY CASE WHERE INSTRUCTIONS ACCOMPANYING AN ISSUE OF A REVISED DRAWING OR SPECIFICATION CHANGE AFFECTS THE COSTS OF THE CONTRACTOR TO REASONABLY PRODUCE THE ALTERATION WITHIN THE AGREED COST, SHALL AFFORD THE CONTRACTOR AN OPPORTUNITY TO SUBMIT ESTIMATES FOR COSTS INVOLVED PRIOR TO

. SUCH ESTIMATES SHALL BE PREPARED AND SUBMITTED PROMPTLY IN ORDER NOT TO UNDULY

3. BEFORE COMMENCING WITH ANY WORK THE CONTRACTOR SHALL FILE WITH THE OWNER CURRENT

INSURANCE CERTIFICATES IN THE AMOUNTS REQUESTED BY THE OWNER FOR WORKMEN'S COMPENSATION, COMPREHENSIVE, GENERAL LIABILITY, BODILY INJURY AND PROPERTY DAMAGE.

4. SUBSTITUTIONS FOR MATERIALS, METHODS, SCHEDULING, AND OF SEQUENCE OF CONSTRUCTION SHALL BE REVIEWED WITH THE OWNER PRIOR TO AWARDING OF THE CONTRACT AND ALL

SUBSTITUTIONS MUST RECEIVE WRITTEN APPROVAL FROM ARCHITECT/OWNER AS APPROVED BY

6. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL OF DEBRIS FROM THE SITE IN

COMMENCEMENT OF SUCH CHANGE.

AFFECT THE PROGRESS OF THE WORK.

REPAIRED AT NO ADDITIONAL COST TO THE OWNER.

ACCORDANCE WITH ALL STATE AND LOCAL GOVERNING AGENCIES.

 INSTALLATION SHALL COMPLY WITH ALL LOCAL AND STATE CODES. THE CONTRACTOR SHALL PAY ALL INSPECTION AND PERMIT FEES. 2. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATION. ALL LABOR MATERIAL AND EQUIPMENT SHALL BE GUARANTEED TO THE OWNER FOR A PERIOD 3. THE CONTRACTOR SHALL COORDINATE ALL WORK WITH OTHER TRADES ESPECIALLY ROUGH 4. THE CONTRACTOR SHALL CONNECT AND INSULATE ALL WATER FEED LINES WITH 1/2" COPPER PIPING. CONTRACTOR CAN SUBSTITUTE WATER LINES WITH PEX PIPING 5. COORDINATE ROUTES OF PLUMBING WITH EXISTING PLUMBING COORDINATE ROUTING WITH CARPENTRY PRIOR TO FRAMING OF WALLS NOTCHED STUDS FOR WASTE AND WATER LINES SHALL BE REINFORCED BY THIS CONTRACTOR WITH NO ADDITIONAL COST TO THE OWNER. REINFORCEMENT OF SAW NOTCH TO BE SPECIFIED AS PER MANUFACTURERS SPECIFICATIONS. 6. ALL PIPING EXPOSED TO POSSIBLE FREEZING WITHIN WALL CAVITIES SHALL BE PROTECTED FROM 7. ALL PLUMBING SYSTEMS SHALL BE TESTED AS SPECIFIED IN THE NATIONAL STANDARD PLUMBING B. VACUUM BREAKERS SHALL BE INSTALLED ON ALL WATER HEATERS SUPPLYING FIXTURES BELOW 9. PLUMBER SHALL OBTAIN INFORMATION FROM THE OWNER AND VERIFY AS TO THE EXACT 10. UNDERGROUND DRAINAGE PIPE AND ALL PIPES 2'-0" ABOVE CONCRETE FLOOR OR LESS SHALL BE CAST IRON. OTHER DRAINAGE PIPES SHALL BE PLASTIC UNLESS OTHERWISE NOTED. SUB CONTRACTOR CAN SUBSTITUTE SCHEDULE 40. 11. WATER PIPES SHALL BE PLASTIC OR COPPER TUBING TYPE L. UNDERGROUND COPPER TUBING SHALL BE JOINT-LESS PIPE TYPE K. ALL WATER PIPING MAINS SHALL BE 3/4" COPPER PIPING. ALL FIXTURE RUNS SHALL BE 1/2". PROVIDE 1/2" AIR POCKETS AT TOP OF WATER LINES. SUB CONTRACTOR CAN SUBSTITUTE PVC. 12. WATER PIPES OVER UNHEATED AREAS SHALL BE RUN WITHIN INSULATED SPACES. 14. VENT TO ROOFS (VTR'S) SHALL BE TIED INTO EXISTING VENTS WHERE POSSIBLE UP TO MAXIMUM 16. UNLESS OTHERWISE NOTED THE WATER HEATER SHALL BE 40 GALLON MINIMUM FOR RESIDENTIAL SEE DEMOLITION NOTES FOR SCOPE OF DEMOLITION. THE INTENT OF THIS SECTION IS TO ALLOW SPECIFICATION OF THE PROPOSED DIFFUSER AND DUCT SYSTEM, AS INDICATED WITHIN THESE ARCHITECTURAL DRAWINGS, TO PRACTICAL INDUSTRY STANDARDS AND ERECTED IN ACCORDANCE WITH INDUSTRY NORMS AND PRACTICAL LIMITATIONS OF THIS ARCHITECTURAL PROJECT. AS SUCH THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THAT THE EXISTING SYSTEM (IF APPLICABLE) OR PROPOSED SYSTEM IS PROPERLY SIZED AND IS OR COULD BE IN WORKING CONDITION TO DERIVE EFFICIENTLY, WITHIN THE PROPOSED LAYOUT, AN EVEN DISTRIBUTION OF THE HEATING, VENTILATION, & AIR CONDITIONING. THE CONTRACTOR SHALL SIZE THE NEW PORTION (WHOLE OR PART) OF THE HVAC SYSTEM BASED ON THE REQUIREMENTS OF THE OWNER, HIS WORK, AND THE SIZE OF THE SPACE. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY HVAC CONTROLLED INSPECTION REPORTS AS REQUIRED BY THE LOCATION AUTHORITIES HAVING JURISDICTION AND PAY FOR ALL INSPECTIONS THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING REQUIRED FOR HIS WORK. NO STRUCTURAL ELEMENTS OR FIRE RATED WALL SHALL BE CUT WITHOUT WRITTEN AUTHORIZATION FROM THE ARCHITECT. CONTRACTOR SHALL ALSO COORDINATE ALL WORK WITH ROUGH CARPENTRY AND VERIFY BY DESIGN ACTUAL SIZE OF DUCT EXTENSIONS WHERE REQUIRED OR SHOWN ON CONSTRUCTION DOCUMENTS DURING FRAMING PHASE. DIFFUSER LOCATIONS IF NOTED ARE "SCHEMATIC" AND ARE INTENDED TO PROVIDE A SUGGESTED LAYOUT. ACTUAL LOCATION SHALL BE BASED ON EXISTING CEILING GRID IN THE CASE OF ADDITION/ALTERATION TO COMMERCIAL WORK, OR PRACTICAL ALIGNMENT WITH EXISTING ELEMENTS OR FIXTURES IN THE CASE OF RESIDENTIAL INSTALLATIONS. 12. EACH CONTRACTOR SHALL GUARANTEE IN WRITING IN A FORM ACCEPTABLE TO THE OWNER,
ALL LABOR AND MATERIALS INSTALLED BY HIM FOR A PERIOD OF NOT LESS THAN ONE YEAR
AFTER DATE OF ACCEPTANCE OF THE WORK BY THE OWNER EXCEPT AS MODIFIED HEREIN OR ON
OTHER DRAWINGS. SHOULD DEFECTS OCCUR ALL WORK SHALL BE REPLACED OR PROPERLY

ELEMENTS OR FIXTURES IN THE CASE OF RESIDENTIAL INSTALLATIONS.

ELEMENTS OR FIXTURES IN THE CASE OF RESIDENTIAL INSTALLATIONS.

FLEXIBLE DUCT WORK SHALL BE INSULATED AND SECURED WITH STEEL DRAW BANDS. THE MAXIMUM LENGTH OF 10" FLEXIBLE DUCTWORK IS 8'-0". 6. CONTRACTOR SHALL BALANCE THIS SYSTEM AT THE COMPLETION OF HIS WORK. ALL HVAC WORK EQUIPMENT AND APPARATUS SHALL CONFORM TO THE REQUIREMENTS OF THE IRC 2009 NJ EDITION AND LOCAL CODES
NATIONAL FIRE PROTECTION ASSOCIATION NFPA
AMCA AIR MOVEMENT AND CONTROL ASSOCIATION INC.
SMACNA SHEET METAL AND AIR CONDITIONING CONTRACTORS NATIONAL ASSOCIATION INC.
ASHRAE— AMERICAN SOCIETY OF HEATING, REFRIGERATION AND AIR CONDITIONING 15. THE CONTRACTORS WITHIN (TEN) CALENDAR DAYS FROM RECEIPT OF DRAWINGS SHALL DELIVER
TO THE OWNER A COMPLETE AND COMPREHENSIVE COST BREAK DOWN OF HIS CONTRACT
PROPOSAL BY TRADES. FURTHERMORE, ALL CONTRACTORS SHALL AGREE TO REVISE HIS COST
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNER AS TO THE CONTENT DISTRIBUTION OF COST,
BREAKDOWN IF NECESSARY TO SATISFY THE OWNE 9. CONTRACTOR SHALL PROVIDE ALL WORK, MATERIAL, AND EQUIPMENT NECESSARY TO FURNISH A

 CONTRACTOR SHALL PROVIDE REROUTING RECONFIGURATION, TESTING, AND ADJUSTMENT FOR BASEBOARD SYSTEM AS REQUIRED TO ACCOMMODATE NEW LAYOUT. 7. EACH SUBCONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ALL DEBRIS CREATED FROM THEIR WORK AND MAINTAINING A SAFE AND CLEAN OPERATION. 18. DO NOT SCALE DRAWINGS. QUESTIONS OR DISCREPANCIES REGARDING DIMENSIONS MUST BE DIRECTED TO THE ARCHITECT IMMEDIATELY. **ELECTRICAL**: DOORS: . INSTALLATION SHALL COMPLY WITH ALL LOCAL, STATE, AND THE LATEST EDITION OF THE NEC. THIS CONTRACTOR SHALL PAY ALL INSPECTION AND PERMIT FEE 2. IN ADDITION / ALTERATION PROPOSALS, THE CONTRACTOR SHALL VERIFY THAT EXISTING CIRCUIT NEW INTERIOR DOORS SHALL BE SELECTED BY THE OWNER IN SIZES INDICATED ON BREAKERS & POWER AVAILABLE IS ADEQUATE TO FULFILL NEEDS OF THE PROPOSED ADDITION , ALTERATION. IN RESIDENTIAL NEW CONSTRUCTION WORK, THE CONTRACTOR SHALL PROVIDE A ARCHITECTURAL DOCUMENTS. UNLESS OTHERWISE NOTED ALL DOORS ARE WOOD SOLID-CORE 200 AMP. THREE PHASE 120/208 VOLT PANEL IN A NON SLEEPING ROOM LOCATED AS CLOSE . NEW INTERIOR DOORS SHALL HAVE KNOCKDOWN FRAMES, EXCEPT WHERE NOTED. 3. MATERIALS, PRODUCTS AND EQUIPMENT INCLUDING ALL COMPONENTS THEREOF, SHALL BE NEW AND SUCH AS APPEAR ON THE UNDERWRITERS LABORATORIES LIST OF APPROVED ITEMS AND SHALL MEET REQUIREMENTS OF NEC, NEMA, AND OTHER RECOGNIZED STANDARDS AND SHALL BE SIZED IN CONFORMITY WITH REQUIREMENTS OF THE LATEST EDITION OF THE NEC. 3. ALL NEW DOOR HARDWARE SHALL MATCH EXISTING AS CLOSELY AS POSSIBLE IN ADDITION/
ALTERATION WORK, OR BE SELECTED BY OWNER IN THE CASE OF NEW CONSTRUCTION WORK.
COMMERCIAL & PUBLIC WORK DOORS & HARDWARE SHALL BE A.D.A. APPROVED LEVER HANDLES
LOCK SETS SELECTED BY OWNER. DOORS CROSSING ANY RATED PARTITION SHALL RECEIVE APPROVED DOOR CLOSURES. ALL DOOR HARDWARE SHALL APPLY TO LATEST CODE. 4. ELECTRIC WIRES SHALL RUN PARALLEL AND PERPENDICULAR TO STRUCTURES. FURTHERMORE ALL HOLES THROUGH STRUCTURE SHALL BE DRILLED AS CLOSE TO THE CENTERLINE OF THE RESPECTIVE STRUCTURAL MEMBER AND AS NEAR TO THE CENTER SPAN OF THE MEMBER AS MOISTURE PROTECTION: CAULK AND SEAL WITH APPROVED MATERIAL ALL JOINTS AND POINTS OF INTERSECTIONS AS REQUIRED TO PROVIDE A POSITIVE BARRIER AGAINST PASSAGE OF MOISTURE AND AIR AT THESE 5 PROVIDE AND INSTALL CONDUITS, PULL WIRED BOXES, COVER PLATES, AND DEVICES, ETC. FOR ALL OUTLETS AS INDICATED. RECEPTACLES & WALL PLATES TO BE IVORY COLOR OR AS SELECTED BY OWNER. FOR BIDDING PURPOSES ASSUME PHENOL WALL PLATES. OPENINGS CAULK SHALL BE LATEX "SONNEBORN" "OFF WHITE" UNLESS OTHERWISE NOTED. 6. ALL THERMOSTATS SHALL BE MOUNTED 4'-0" A.F.F. TO CENTERLINE UNLESS OTHERWISE NOTED. **DEMOLITION:** ALL OUTLETS OTHER THAN THOSE CALLED FOR AT INSTALLATIONS ABOVE A SINK OR COUNTER, OR AT INSTALLATIONS BEHIND FIXED APPLIANCES OR MECHANICAL EQUIPMENT SHALL BE WHERE EXISTING WORK IS TO BE CUT, CONTRACTOR SHALL PROVIDE ALL UNDERPINNING, LOCATED 1'-0" A.F.F. TO CENTER UNLESS OTHERWISE NOTED. WHERE EXISTING WORK IS TO BE COT, CONTRACTOR SHEEDING, BRACING, WEDGING AND DRY —PACKING PRIOR TO COMMENCEMENT.

CONTRACTOR SHALL PROTECT ALL EXISTING STRUCTURES / PROPERTY DURING THE COURSE OF CONSTRUCTION FROM THE ELEMENTS AND SHALL REPAIR ALL ITEMS DAMAGED DUE TO HIS

CONSTRUCTION FROM THE ELEMENTS AND SHALL REPAIR ALL ITEMS DAMAGED DUE TO HIS 8. ALL SWITCHES SHALL BE 4'-0" A.F.F. TO CENTER UNLESS OTHERWISE NOTED. CONSTRUCTION FROM THE ELEMENTS AND SHALL REPAIR ALL ITEMS DAMAGED DUE TO HIS NEGLECT OR FAILURE TO PROPERLY PROTECT SAID STRUCTURE / PROPERTY DURING ALL PHASES OF DEMOLITION AND CONSTRUCTION. GENERAL CONTRACTOR SHALL MAINTAIN STRUCTURAL INTEGRITY OF STRUCTURES TO BE DEMOLISHED AND ANY ADJACENT FACILITIES TO REMAIN WITH INTERIOR OR EXTERIOR SHORING, BRACING OR SUPPORT TO PREVENT MOVEMENT, SETTLEMENT OR COLLAPSE OF STRUCTURES. THE LOCATION OF NEW OUTLETS SHOWN ON DRAWINGS ARE SCHEMATIC UNLESS EXPLICITLY DIMENSIONED. THE FINAL LOCATION TO BE COORDINATED WITH OWNER PRIOR TO INSTALLATION COORDINATE WITH CARPENTRY THE REQUIRED BLOCKING FOR EXACT LOCATION OF DEVICE. 10. NO FLOOR OR WALL OUTLETS SHALL BE CONNECTED TO LIGHTING CIRCUITS. THE ELECTRICIAN SHALL COORDINATE CIRCUITING BASED ON THE NATIONAL ELECTRIC CODE. VERIFY ALL DIMENSIONS AT SITE PRIOR TO START OF CONSTRUCTION. SHOULD CONTRACTOR VERIFY ALL DIMENSIONS AT SITE PRIOR TO STANT OF CONTROL OF CONSTRUCTION PRIOR TO FIELD DIMENSION VERIFICATION VERIFICATION AND SUCH DIMENSION AS IT APPEARS ON THE ARCHITECTURAL DRAWING IS WRONG, THEN THE CONTRACTOR ALL ELECTRIC EQUIPMENT SHALL BE INSTALLED BY A NJ LICENSED ELECTRICIAN. NO OTHER INDIVIDUAL HOWEVER QUALIFIED SHALL PERFORM ANY ELECTRICAL WORK WITHIN THESE PLANS. SHALL BE HELD RESPONSIBLE FOR THE CORRECTION AND / OR REPAIR. THE CONTRACTOR IS RESPONSIBLE FOR THE SAFETY OF THE STRUCTURE DURING THIS OPERATION 12. SHOULD JOB CONDITIONS REQUIRE THE RELOCATION OF PLANNED TELEPHONE OR ELECTRICAL OUTLETS FOR ANY REASON, THAN THE CONTRACTOR SHALL NOTIFY THE ARCHITECT AND/ OR OWNER FOR APPROVAL BEFORE RELOCATING THE SERVICES. AND THE COORDINATION OF THE DEMOLITION WORK WITH OTHER TRADES. CONTRACTOR SHALL BE REQUIRED TO REPAIR AND PATCH ANY AREAS THAT ARE ALTERED OR 13. THE ELECTRICIAN SHALL BE RESPONSIBLE FOR WIRE SIZING, ROUTING AND CIRCUITING OF NEW ELECTRICAL SERVICE, IF NEW ELECTRIC SERVICE IS CALLED FOR. DAMAGED DUCTING THE PROCESS OF THE ALTERATION. DISCONNECT ALL ELECTRICAL, MECHANICAL, AND PLUMBING AS REQUIRED FOR DEMOLITION WORK. 14. ALL TELEPHONE WORK SHALL BE COORDINATED WITH A TELEPHONE COMPANY REPRESENTATIVE AFTER DEMOLITION, PRIOR TO NEW CONSTRUCTION, ARCHITECT TO INSPECT ALL DEMOLITION. DEMOLITION CONTRACTOR TO NOTIFY ARCHITECT IF THERE IS ANY QUESTION ON STRUCTURAL INTEGRITY AFTER UNDERPINNING, SHORING, NEEDLING, BRACING, WEDGING AND DRY PACKING ARE PERFORMED. 15. IF OUTLET DIMENSIONS CALL FOR A MOUNTING HEIGHT GREATER THAN 24" ABOVE THE FINISHED FLOOR THEN THE OUTLETS SHALL BE MOUNTED HORIZONTALLY UNLESS OTHERWISE NOTED. ALL 125 VOLT, SINGLE PHASE, 15 & 20 AMP OUTLETS ABOVE A COUNTERTOP AND WITHIN 6'-0"
OF A WATER SUPPLY SHALL BE G.F.I. OUTLETS. ALL 125 VOLT, SINGLE PHASE, 15 & 20 AMP
OUTLETS WITHIN THE GARAGE, CRAWL SPACE, BATHROOM, UNFINISHED BASEMENT AND ANY
OUTDOOR OUTLETS SHALL BE GROUND FAULT INTERRUPT UNLESS OTHERWISE NOTED WITHIN THE DRYWALL & CAVITY ASSEMBLIES: ARCHITECTURAL DRAWINGS. ALL OTHER OUTLETS UNLESS OTHERWISE NOTED SHALL BE ALL INTERIOR WALL CAVITIES BETWEEN FLOORS SHALL BE FIRESTOPPED. ALL WOOD FIRE STOPPING SHALL BE FIRE TREATED LUMBER. IN THE CASE WHERE WOOD FIRE STOPPING CANNOT BE COMPLETED, SUBCONTRACTOR CAN USE FIRE RETARDANT MINERAL WOOL IN LIEU OF FIRE 17. ALL EXISTING WALL OUTLETS, WHICH DO NOT INTERFERE WITH NEW CONSTRUCTION SHALL REMAIN. ANY EXISTING ELECTRICAL DEVICE WHICH INTERFERES WITH THE NEW PARTITION WORK STOPPING. CONTRACTOR TO VERIFY RATING AS PER MANUFACTURER'S SPECIFICATIONS. SHALL BE RELOCATED TO A LOCATION APPROVED BY THE OWNER. ALL GYPSUM WALL BOARD UNLESS OTHERWISE NOTED SHALL BE 1/2" THICKNESS. ALL GYPSUM 18. THE CONTRACTOR SHALL RECEIVE, HANDLE, ASSEMBLE, INSTALL ALL ELECTRICAL FIXTURES AND CONNECT LIGHT FIXTURES, INCLUDING INITIAL LAMPS, COMPLIANT WITH UL RATING. ALL LIGHT FIXTURES TO BE SELECTED BY OWNER. WALL BOARD IN BASEMENT SHALL BE MOISTURE RESISTANT. DURAROCK CEMENT BOARD APPLIED

PLUMBING:

OF ONE (1) YEAR FROM THE DATE OF INSTALLATION.

FREEZING. PLUMBER TO NOTIFY ARCHITECT IF FREEZING MAY OCCUR.

CODE CHAPTER 15 PARAGRAPH 15:1 THROUGH 15:6.

LOCATION THE SIZE OF THE EXISTING SANITARY SYSTEM.

13. EACH FIXTURE GROUP SHALL HAVE SEPARATE TURNOFF VALUES.

15. HORIZONTAL PIPING RUNS SHALL PITCH 1/4" OVER 12'-0".

ELEVATIONS OF BASE OF WATER HEATERS.

OF THREE (3) FIXTURES FOR 3" VENTS.

FOLLOWING: IRC 2009 NJ EDITION AND LOCAL CODES

CONTROL WIRING BY HVAC CONTRACTOR.

COMPLETE SYSTEM AS PER CODE.

ASTM- AMERICAN SOCIETY FOR TESTING MATERIALS

SITE PROBLEMS SUCH AS SURFACE WATER, SUB SURFACE WATER, ROCK, POOR SOIL NOTIONS, BACKFILL MATERIAL, ETC., AND CONSTRUCTION MODIFICATIONS TO ACCOMMODATE ATED PROBLEMS SHALL BE THE RESPONSIBILITY OF OTHERS. CODES REFERENCED: LOCAL BUILDING CODES & ORDINANCES
INTERNATIONAL BUILDING CODE — NJ EDITION 2021
INTERNATIONAL RESIDENTIAL CODE — NJ EDITION 2021
REHABILITATION SUBCODE — NJAC: 5: 23—6
BARRIER—FREE SUBCODE — NJAC: 5: 23—7 — ANSI A117.1—2017
NATIONAL FIRE PROTECTION ASSOCIATION REFERENCED STANDARDS
NATIONAL STANDARD PLUMBING CODE — 2021 NATIONAL STANDARD PLOMBING CODE = 2021

NATIONAL ELECTRIC CODE = 2020

INTERNATIONAL ENERGY CONSERVATION CODE = 2021 WITH RESCHECK

INTERNATIONAL MECHANICAL CODE = 2021

INTERNATIONAL FUEL GAS CODE = 2021

ALL FOOTINGS SHALL BEAR ON UNDISTURBED EARTH CAPABLE OF SUPPORTING 2 TONS PER SQUARE FOOT. SPECIFIC SOIL CONDITIONS AT VARIANCE WITH THIS REQUIREMENT SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER BY THE CONTRACTOR, IF NO SOIL TESTING OR SITE STUDIES ARE PERFORMED BY THE OWNER OR ARE NOT PROVIDED FOR HIS USE, RESPONSIBILITY

SOIL BEARING CAPACITY:

PROPOSED DECK +ADDITION 563 SF EXISTING DECK TO BE DEMO'D:-514 SF Lot 25 Lot 24 Lot 23 Block 41 Block 41 Block 41 ~~~~~~ (TM) PROPOSED BUILDING N 59°31'00"W 52.00' Iron Pipe Found FOOTPRINT: 1,240SF 0.60' REQUIRED DECK AT - 3 3 20%(1,240SF) = 248SFPROPOSED DECK: 234 SF < 248 SF 10 N Second . TOTAL COVERAGE Lot 16 Lot 17 Lot 18 Block 41 **BUILDING+DECK** Block 41 Block 41 (TM) ,240+234=1,474SF 0 (TM) 0 M Lot 16 Lot 18 Block 15H Lot 17 Block 15H (FM) Block 15H (FM) 25'-8 1/2" 0 M 234 SF DECK **ADDITION** 329 SF Concrete **EXISTING ADDITION PROPOSED** ROOF PEAK: 130' 0.9 **NEW A.C. CONDENSER** FIRST FLOOR: 102' ROOF Story Frame 2 Story 2 Stor Dwelling Frame Frame Dwelling No. 9 85.5 SF - DWEYTRO EXISTING A.C 2ND FL ADD A CONDENSER TO BE REPLACED LEVEL ADDITION Porch ~~~~ TOP OF LANDING: 102' **18SF CONDENSOR** PAD FOR NEW A. BOTTOM OF LANDING: 100' **EXISTING 797 SF** WALKWAY/DRIVEWAY Aspholt Driveway 850.00' to Wildwood Terroce S 59°31'00"E 52.00' Concrete Walk SCALE-1"=10" Concrete Curb This survey certified to: Brentwood Drive John Norris and Krisin Norris ium Home Mortgage, LLC, its successors and/or assigns as their interest may appear Able Title Agency, LLC Wastene Land Title Incurance Company

1 SITE SURVEY

NO TREE REMOVAL REQUIRE

THIS IS EXEMPT FOR STORMWATER MANAGEMENT

1" = 10'-0"

SCHEDULE OF SPACE REGULATIONS CITY OF VERONA, ESSEX COUNTY, NJ REQUIRED EXISTING PROPOSED ZONE R-50 IIN. SIZE OF LOT FRONT YARD (FT. MINIMUM PRINCIPAL REQUIRED YARD BUILDING DEPTH (FT) BOTH SIDE YARDS % OF LOT WIDTH MAXIMIM HEIGHT MAX. % OF LOT COVERAGE MAX. % IMPROVED LOT COVERAGE CONSTRUCTION CLAS 28,608 CU OTAL VOLUME (CU.FT OTAL SQUARE FOOTAGE (SQ.I NOTES: CODES REFERENCED IRC 2021 NJ EDITION 1. ALL LUMBER SHALL BE DOUGLAS FIR #2. 3. LOCATE SMOKE DETECTORS IN ALL BEDROOMS, HALLWAY AREA STAIRCASE, AND IN FINISHED ATTICS. SMOKE DETECTORS SHALL BE HARDWIRED W/ BATTERY BACKUP HOUSE IS MORE THEN OR EQUAL TO 25% OF LARGEST FLOOR AREA. 4. CARBON MONOXIDE DETECTORS SHALL BE LOCATED OUTSIDE OF ALL SLEEPING ROOMS WITHIN A DISTANCE OF 10 FEET DESIGN LOADS ROOF/SNOW 110 MPH ASSUMED SCOPE OF WORK: PROPOSAL FOR INTERIOR ALTERATIONS AND ADDITION ON AN EXISTING SINGLE-FAMILY FRAMED DWELLING AS DESCRIBED WITHIN THESE CONSTRUCTION DOCUMENTS. AVERAGE GRADE CLACS POINT 1: 100 POINT 2: 100 POINT 3: 100 7 POINT 4: 100 POINT 5: 100' POINT 6: 100.2 POINT 7: 100.3 POINT 8: 100' POINT 9: 100' POINT 10: 99.8 POINT 11: 99.8 POINT 12: 100' POINT 13: 99.7 POINT 14: 99.8 POINT 15: 100.2' POINT 16: 100.2' POINT 17: 100' POINT 18: 100' TOTAL:1800'/18 POINTS **AVERAGE GRADE:100** ROOF PEAK: 130' 130'-100'=30' (BULK HEIGHT) EXISTING VOLUME (CU.FT.) PROPOSED VOLUME (CU.FT.) TOTAL VOLUME (CU.FT. 19,665 CU 8,943 CU 28,608 CU EXISTING SQUARI PROPOSED SQUARE TOTAL SQUARE FOOTAGE (SO.FT.) FOOTAGE (SQ.FT.) FOOTAGE (SO.FT.) 745 SF 1.639 SF EXISTING BUILDING COVERAGE PROPOSED BUILDING COVERAGE **EXISTING+PROPOSED ADDITION: 1,240SF EXISTING HOUSE: 911SF** EXISTING DECK (TO BE REMOVED):514SI PROPOSED DECK: 234SF TOTAL:1,425SF (1,425/6,509= 21.9%) TOTAL:1,474SF (1,474/6,509= 22.6%) EXISTING IMPER. COVERAGE BREAKDOWN PROPOSED IMPER. COVERAGE BREAKDOWN **EXISTING HOUSE: 911SF** EXISTING+PROPOSED ADDITION: 1,240SF

THE REPORT OF THE PERSON OF TH THE RESERVE 5.9.23 ZONING REVISION 2.09.23 AVERAGE GRADE 5.9.23 REPLACE A/C CONDENSE 5.9.23 NEW A/C CONDENSER 4.18.23 UPDATED CODES 5.9.23 TREE REMOVAL/ STORMWATER NOTE 5.9.23 A/C CONDENSER PAD DWG BY DAV CHECK T RAWINGS NOT VALL TTHOUT RAISED SEA DATE: 03.28.2023 CALE: AS NOTED DWG: ZONING INFO OB NO.: 22-022 EXISTING DECK (TO BE REMOVED):514SI PROPOSED DECK: 234SF EXISTING DRIVEWAY/WALKWAY:797SF EXISTING DRIVEWAY/WALKWAY:797SF

PROPOSED AC CONDENSER: 18SF

TOTAL:2,280SF (2,289/6,509= 35.1%)

TOTAL:2,222SF (2,222/6,509= 34.1%)

2

3. ALL GYPSUM SURFACES SHALL RECEIVE A HEAVY BONDED PRIMER SEALER COAT SIMILAR OR EQUAL TO "U.S. GYPSUM". ALL PAINT SHALL BE THOROUGHLY MIXED. THE MIXTURE SHALL BE ONE COAT COLOR AND CONSISTENCY. ALL COLORS SHALL BE SELECTED BY THE OWNER UNLESS OTHERWISE NOTED PAINTING SUB SHALL BID PAINT TO FLAT CEILING AND MATTE WALLS. OWNER TO SPECIFY.

. PROTECT ALL WORK BEFORE, DURING AND AFTER DEMOLITION AND INSTALLATION.

ALL METAL STUD WORK SIZES FOR NON-LOAD BEARING WALLS, UNLESS OTHERWISE NOTED,

NOTIFY ARCHITECT IMMEDIATELY.

BY THE MANUFACTURE'S SPECIFICATIONS.

CONTRACTOR UNLESS UNDER SEPARATE AGREEMENT.

. SCREW AND GLUE ALL FLOORING PLYWOOD SHEATHING.

FINISHES:

SHALL BE 25 GAUGE "ST25" STUDS OR BETTER, AND "CR25" RUNNERS FOR TOP AND BOTTOM PLATES OR BETTER. ALL METAL STUD WORK SIZES FOR LOAD BEARING WALLS, MUST BE NOTED ON THE PLANS. IF SPECIFIC REFERENCE REMAINS ON-SPECIFIC WITHIN THESE PLANS PLEASE

4. ALL WOOD STUD WALL ASSEMBLIES, UNLESS OTHERWISE NOTED, SHALL BE CONSTRUCTED OF 2" X 4" WOOD STUDS AT 16" O.C. WITH A (2) 2" X 4" WOOD TOP AND (1) 2" X 4" BOTTOM PLATE TOE—NAILED BETWEEN STUD & PLATE.

ALL GYPSUM WALL & CEILING BOARD SHALL BE BY "U.S. GYPSUM COMPANY" OR APPROVED EQUAL. ALL SIZES AND LOCATIONS SHALL BE REFERENCED FROM THE ARCHITECTS DRAWINGS

ALL DRYWALL SHALL BE INSTALLED WITH DRYWALL SCREWS. SIZES SHALL BE AS RECOMMEN

ALL EXISTING CEILING TILES SHALL REMAIN UNLESS AS REQUIRED TO FULFILL THE INTENT OF T ARCHITECT'S DRAWINGS. IN THE EVENT THAT TILES MUST BE REMOVED MATCHING TILES SHALL BE PROVIDED.

TAPE, SPACKLE 3 COATS WITH MANUFACTURE DRYING TIME SPECIFICATIONS, SAND AND PRIME

ALL GYPSUM WORK READY FOR PAINT FINISH. ALL PAINTING SHALL BE PERFORMED BY THE

PROVIDE A MINIMUM OF THREE (3) COATS OF JOINT COMPOUND OVER SCREWS HEADS AT JOINT. APPLY JOINT COMPOUND THEN TAPE, AND COVER WITH JOINT COMPOUND. ALLOW TO DRY THEN

APPLY JOINT COMPOUND AGAIN. SAND ALL JOINT COMPOUND AREAS SMOOTH (IF NECESSARY). TAKE CARE NOT TO "DAMAGE" GYPSUM BOARD PAPER. DAMAGE SHALL BE BROUGHT TO ARCHITECT.

10. ALL FLOORING UNLESS OTHERWISE NOTED SHALL BE SELECTED BY THE OWNER.