BOSWELL


Boswell Capital Improvement Projects


Verona Township Council Meeting


A CENTURY OF EXCELLENCE

Engineered For Life









BANK STABILIZATION ALONG THE PECKMAN RIVER BLOCK 1703 LOTS 54, 55, 56, 59, 60

TOWNSHIP OF VERONA

Essex County, New Jersey

MAYOR
CHRISTOPHER TAMBURRO

TOWNSHIP OF VERONA

COUNCIL MEMBERS

JACK MCEVOY

CHRISTINE MCGRATH

CYNTHIA HOLLAND

ALEX ROMAN


TOWNSHIP MANAGER
JOSEPH D'ARCO

TOWNSHIP CLERK JENNIFER KIERNAN

TOWNSHIP ATTORNEY BRIAN J. ALOIA, ESQ

TOWNSHIP ENGINEER
BOSWELL ENGINEERING

| PUBLIC UTILITIES LIST | | | |
|-----------------------|---------------------------------------|--|--|
| CABLE | COMCAST | | |
| ELECTRICITY | PUBLIC SERVICE ELECTRIC & GAS COMPANY | | |
| GAS | PUBLIC SERVICE ELECTRIC & GAS COMPANY | | |
| TELEPHONE | VERIZON | | |
| WATER | MONTCLAIR WATER DEPARTMENT | | |



| PROJECT LOCATION MAP | |
|----------------------|--|
| 1" = 500' | |

| INDEX OF SHEETS | | | |
|-----------------|---|--|--|
| SHEET NUMBER | SHEET TITLE | | |
| 1 | TITLE SHEET | | |
| 2 | EXISTING PLAN | | |
| 3 | SITE PLAN | | |
| 4 | ENVIRONMENTAL PLAN | | |
| 5 | CROSS SECTIONS -1 | | |
| 6 | CROSS SECTIONS - 2 | | |
| 7 | SWALE CROSS SECTIONS | | |
| 8 | PLANTING PLAN | | |
| 9 | CONSTRUCTION DETAILS | | |
| 10 | SOIL EROSION AND SEDIMENT CONTROL PLAN | | |
| 11 | SOIL EROSION AND SEDIMENT CONTROL DETAILS | | |
| | | | |


BOSWELL ENGINEERING
330 PHILLIPS AVENUE


SOUTH HACKENSACK, NEW JERSEY 07606
Tel (201) 641-0770 . Fax (201) 641-1831
NJ Certificate of Authorization No. 24GA27958000


KEVIN J. BOSWELL
PROFESSIONAL ENGINEER N.J. LIC. 32943


JOSEPH A. POMANTE PROFESSIONAL ENGINEER N.J. LIC. 43137 JOB NO. VA-102 OCTOBER 20, 2023 VA-102-TS


SHEET 1 OF 11














GRAPHIC SCALE (IN FEET) 1 inch = 20 feet

- PLAN NOTES:
 1. BASEMAP REFERENCES SURVEY PERFORMED BY BOSWELL ENGINEERING, WHICH IS SUPPLEMENTED BY LIDAR TOPOGRAPHY.
- 2. VERTICAL DATUM IS NAVD 88. TO CONVERT FROM NAVD 88 TO NGVD 29, ADD 0.912
- 3. HORIZONTAL DATUM IS NAD 83 4. PARCEL BOUNDARIES DEPICTED WERE OBTAINED FROM NJ GIS DATABASE







| 2 | 04/11/25 | REVISED PER DEP COMMENTS | | RX | RX | FJR |
|-----|----------|--------------------------|----------------|-------------|----------------|---------------|
| 1 | 05/06/24 | REVISED PER DEP COMMENTS | | LLJ | RX | FJR |
| NO. | DATE | DESCRIPTION | SURVEYED BY | DRAWN BY | DESIGNED BY | CHECKED BY |
| | • | | • | - | | |




| KEVIN J. BOSWELL | JOSEPH A. POMANTE | |
|---------------------------------------|---------------------------------------|--|
| | | |
| | | |
| PROFESSIONAL ENGINEER N.J. LIC. 32943 | PROFESSIONAL ENGINEER N.J. LIC. 43137 | |

| BANK STABILIZATION ALONG THE PECKMAN RIVER BLOCK 1703 LOT 54, 55, 56, 59, 60 CROSS SECTIONS — 2 | | | | |
|---|----------------------------------|--------------------|-------------------|------------------|
| TOWNSHIP OF VERONA | | | | |
| ESSEX COUNTY | | | NEW | JERSEY |
| SURVEYED BY DRAWN BY RX | DESIGNED BY SJ CHECKED BY FJR | SCALE: AS NOTED | JOB NO. VA-102 | DATE 10/20/23 |

DRAWING NO. VA-102-CP.DWG

SHEET 6 of $1\overline{1}$



STA:: 0+25

340

GEOTEXTILE FABRIC

2 LAYERS RIP-RAP STONE
D50=8" 16" THICK


SECTION VIEW


PLAN NOTES:

1. BASEMAP REFERENCES SURVEY PERFORMED BY BOSWELL ENGINEERING, WHICH IS SUPPLEMENTED BY LIDAR TOPOGRAPHY.


2. VERTICAL DATUM IS NAVD 88. TO CONVERT FROM NAVD 88 TO NGVD 29, ADD 0.912

3. HORIZONTAL DATUM IS NAD 83
4. PARCEL BOUNDARIES DEPICTED WERE
OBTAINED FROM NJ GIS DATABASE





PROFILE VIEW



| | | НО | RIZON | NTAL SCALE | |
|---|---|-----|-------|----------------|----|
| 5 | 0 | 2.5 | 5 | 10 | 20 |
| | | | • | FEET) = 5 ft. | |

| 3 | 04/11/25 | REVISED PER DEP COMMENTS | | RX | RX | FJR |
|-----|----------|--------------------------|----------------|-------------|----------------|---------------|
| 2 | 05/07/24 | REVISED PER DEP COMMENTS | | LLJ | RX | FJR |
| 1 | 05/06/24 | REVISED PER DEP COMMENTS | | LLJ | RX | FJR |
| NO. | DATE | DESCRIPTION | SURVEYED BY | DRAWN BY | DESIGNED BY | CHECKED BY |
| | | | | | | |

| | Boswell Engineering |
|-----------|--|
| EST. 1924 | ENGINEERS - PLANNERS - SURVEYORS - SCIENTISTS 330 PHILLIPS AVENUE, SOUTH HACKENSACK, NJ 07606 TEL: (201) 641-0770 ● FAX: (201) 641-1831 N.J. CERTIFICATE OF AUTHORIZATION No. 24GA27958000 |

| KEVIN J. BOSWELL | JOSEPH A. POMANTE |
|------------------|-------------------|
| | |
| | |

PROFESSIONAL ENGINEER N.J. LIC. 32943

| BANK STAE | BILIZATION ALONG | THE PECK | KMAN R | IVER |
|--------------|-------------------|------------|-----------|--------|
| BLOC | CK 1703 LOT 54, 5 | 55, 56, 5° | 9, 60 | |
| | SWALE CROSS | SECTION | \bigvee | |
| | TOWNSHIP OF V | ERONA | | |
| ESSEX COUNTY | | | NEW | JERSE' |
| CUDVEVED BY | DESIGNED BY SI | SCALE. | IOD NO | DATE |

PROFESSIONAL ENGINEER N.J. LIC. 43137

ESSEX COUNTY


SURVEYED BY DESIGNED BY SJ CHECKED BY FJR


DRAWN BY RX


DRAWING NO. VA-102-CP.DWG


NEW JERSEY


JOB NO. DATE
10/20/23











APPROVED SUBGRADE

SITE SPECIFIC GEOTEXTILE (TURN ENDS UP)

TOP TERMINATION

N.T.S

4,000 PSI CONCRETE,

— GROUT, OR OTHER

(AS SPECIFIED BY EOR)

4,000 PSI CONCRETE,
GROUT, OR OTHER
(AS SPECIFIED BY EOR)

APPROVED
SUBGRADE

SITE SPECIFIC
GEOTEXTILE
(TURN ENDS UP)

FLANK TERMINATION

NOTES:

1. ARTICULATED CONCRETE BLOCK MATTING, OPEN CELL, ARMORFLEX CLASS 70 LARGE BY CONTECH ENGINEERED SOLUTIONS, LLC. (WEST CHESTER OH) OR APPROVED EQUAL.


ARMORFLEX

CONCRETE MATTRESS

 NO SEPARATE PAYMENT WILL BE MADE FOR GEOTEXTILE OR CONCRETE UTILIZED FOR TERMINATIONS AS SHOWN ABOVE, BUT THE COST SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ARTICULATED CONCRETE BLOCK MATTING, OPEN CELL.

ARTICULATED CONCRETE BLOCK MATTING, OPEN CELL

N.T.S.





| KEVIN J. BOSWELL | JOSEPH A. POMANTE |
|------------------|-------------------|
| | |
| | |


BANK STABILIZATION ALONG THE PECKMAN RIVER BLOCK 1703 LOT 54, 55, 56, 59, 60 DETAIL SHEET

TOWNSHIP OF VERONA

| ESSEX COUNTY | | | NEW | JERSEY |
|----------------------------|----------------------------------|--------------------|-------------------|------------------|
| SURVEYED BY DRAWN BY RX | DESIGNED BY SJ CHECKED BY FJR | SCALE: AS NOTED | JOB NO. VA-102 | DATE 10/20/23 |
| DRAWING NO. VA-102- | -ENV.DWG | Si | неет 9 | of 11 |

PROFESSIONAL ENGINEER N.J. LIC. 32943

PROFESSIONAL ENGINEER N.J. LIC. 43137



SOIL EROSION NOTES

- 1. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ON THIS PLAN WILL BE CONSTRUCTED IN ACCORDANCE WITH THE "NEW JERSEY STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL" 7TH EDITION LAST REVISED DECEMBER 2017 THESE MEASURES WILL BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCE OR IN THEIR PROPER SEQUENCE AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.
- 2. ALL SOIL TO BE EXPOSED OR STOCKPILED FOR A PERIOD OF GREATER THAN 14 DAYS, AND NOT UNDER ACTIVE CONSTRUCTION, WILL BE TEMPORARILY SEEDED AND HAY MULCHED OR OTHERWISE PROVIDED WITH VEGETATIVE COVER. THIS TEMPORARY COVER SHALL BE MAINTAINED UNTIL SUCH TIME WHEREBY PERMANENT RESTABILIZATION IS ESTABLISHED.
- SEEDING DATES: THE FOLLOWING SEEDING DATES ARE BEST RECOMMENDED TO ESTABLISH PERMANENT VEGETATIVE COVER WITHIN MOST LOCATIONS IN THE HEPSCD: <u>SPRING - 3/1 TO 5/15</u> AND <u>FALL - 8/15 TO 10/01</u>
- 4. SEDIMENT FENCES ARE TO BE PROPERLY TRENCHED AND MAINTAIN UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.
- 5. ALL STORM DRAINAGE INLETS SHALL BE PROTECTED BY ONE OF THE PRACTICES ACCEPTED IN THE STANDARDS AND PROTECTION SHALL REMAIN UNTIL PERMANENT STABILIZATION HAS BEEN ESTABLISHED. STORM DRAINAGE OUTLET POINTS SHALL BE PROTECTED AS REQUIRED BEFORE THEY BECOME FUNCTIONAL
- 6. MULCH MATERIALS SHALL BE UN-ROTTED SMALL GRAIN STRAW APPLIED AT THE RATE OF 70-90 POUNDS PER 1,000 SQUARE FEET AND ANCHORED WITH A MULCH ANCHORING TOOL, LIQUID MULCH BINDERS, OR NETTING TIE DOWN. OTHER SUITABLE MATERIALS MAY BE USED IF APPROVED BY THE SOIL CONSERVATION DISTRICT.
- 7. ALL EROSION CONTROL DEVICES SHALL BE PERIODICALLY INSPECTED, MAINTAINED AND CORRECTED BY THE CONTRACTOR. ANY DAMAGE INCURRED BY EROSION SHALL BE RECTIFIED IMMEDIATELY.
- 8. THE HUDSON-ESSEX-PASSAIC SOIL CONSERVATION DISTRICT WILL BE NOTIFIED IN WRITING AT LEAST 48 HOURS PRIOR TO ANY SOIL DISTURBING ACTIVITIES. FAX -(862) 333-4507. EMAIL - INFORMATION@HEPSCD.ORG.
- 9. THE APPLICANT MUST OBTAIN A DISTRICT ISSUED REPORT-OF-COMPLIANCE PRIOR O APPLYING FOR THE CERTIFICATE OF OCCUPANCY OR TEMPORARY CERTIFICATE OF OCCUPANCY FROM THE RESPECTIVE MUNICIPALITY, NJ-DCA OR ANY OTHER CONTROLLING AGENCY. CONTACT THE DISTRICT AT 862-333-4505 TO REQUEST A FINAL INSPECTION, GIVING ADVANCED NOTICE UPON COMPLETION OF THE RESTABILIZATION MEASURES. A PERFORMANCE DEPOSIT MAY BE POSTED WITH THE DISTRICT WHEN WINTER WEATHER OR SNOW COVER PROHIBITS THE PROPER APPLICATION OF SEED, MULCH, FERTILIZER OR HYDRO-SEED.
- 10. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES. DO NOT UTILIZE A FIRE OR GARDEN HOSE TO CLEAN ROADS UNLESS THE RUNOFF IS DIRECTED TO A PROPERLY DESIGNATED AND FUNCTIONING SEDIMENT BASIN. WATER PUMPED OUT OF THE EXCAVATED AREAS CONTAINS SEDIMENTS THAT MUST BE REMOVED PRIOR TO DISCHARGING TO RECEIVING BODIES OF WATER USING REMOVABLE PUMPING STATIONS, SUMP PITS, PORTABLE SEDIMENTATION TANKS AND/OR SILT CONTROL
- 11. ALL SURFACES HAVING LAWN OR LANDSCAPING AS FINAL COVER ARE TO BE PROVIDED TOPSOIL PRIOR TO RE-SEEDING. SODDING OR PLANTING. A DEPTH OF 5.0 INCHES, FIRMED IN PLACE, IS REQUIRED, AS PER THE STANDARDS FOR TOPSOILING AND LAND GRADING, LAST REVISED DECEMBER, 2017.
- 12. ALL PLAN REVISIONS MUST BE SUBMITTED TO THE DISTRICT FOR PROPER REVIEW AND APPROVAL.
- 13. A CRUSHED STONE WHEEL CLEANING TRACKING-PAD IS TO BE INSTALLED AT ALL SITE EXITS USING 2-1/2 - 1" CRUSHED ANGULAR STONE (ASTM 2 OR 3) TO A MINIMUM LENGTH OF 50 FEET AND MINIMUM DEPTH OF 6". ALL DRIVEWAYS MUST BE PROVIDED WITH CRUSHED STONE UNTIL PAVING IS COMPLETE.
- 14. STEEP SLOPES INCURRING DISTURBANCE MAY REQUIRE ADDITIONAL STABILIZATION MEASURES. THESE "SPECIAL" MEASURES SHALL BE DESIGNED BY THE APPLICANT'S ENGINEER AND BE APPROVED BY THE SOIL CONSERVATION DISTRICT
- 15. THE HUDSON-ESSEX-PASSAIC SOIL CONSERVATION DISTRICT SHALL BE NOTIFIED, IN WRITING, FOR THE SALE OF ANY PORTION OF THE PROJECT OR FOR THE SALE OF INDIVIDUAL LOTS. NEW OWNERS' INFORMATION SHALL BE PROVIDED. ADDITIONAL MEASURES DEEMED NECESSARY BY DISTRICT OFFICIALS SHALL BE IMPLEMENTED AS CONDITIONS WARRANT.

PLANTING NOTES

- 1. THE CONTRACTOR SHALL FURNISH AND PLANT ALL PLANTS SHOWN ON THE DRAWINGS, AS SPECIFIED, AND IN QUANTITIES INDICATED ON THE PLANT LIST.
- 2.ALL PLANTS SHALL BE NURSERY GROWN, AND HAVE A MEASUREMENT AND SIZE IN ACCORDANCE WITH THE AMERICAN STANDARD FOR NURSERY STOCK, LATEST EDITION AS PUBLISHED BY AMERICAN HORT. ONLY NURSERY GROWN PLANT MATERIALS SHALL BE ACCEPTABLE.
- 3.ALL PLANTS SHALL BE TYPICAL OF THEIR SPECIES OR VARIETY AND SHALL HAVE A NORMAL OR HEAVY HABIT OR GROWTH. THEY SHALL BE SOUND, HEALTHY AND VIGOROUS, WELL BRANCHED AND DENSELY FOLIATED WHEN IN LIFE. THEY SHALL BE FREE OF DISEASE AND INSECT PESTS, EGGS OR LARVAE. THEY SHALL HAVE HEALTHY WELL-DEVELOPED ROOT SYSTEMS.
- 4.SUBSTITUTIONS: WHEN PLANTS OF A SPECIFIC KIND OR SIZE ARE NOT AVAILABLE WITHIN A REASONABLE DISTANCE, SUBSTITUTIONS MAY BE MADE UPON REQUEST BY THE CONTRACTOR IN WRITING, IF APPROVED BY THE OWNER OR HIS REPRESENTATIVE & THE MUNICIPALITY. THE CONTRACTOR SHALL NOTIFY THE OWNER IN WRITING OF ANY PLANT MATERIALS WHICH HE FEELS WILL NOT BE AVAILABLE OR LIKELY TO THRIVE IN THE LOCATION INDICATED ON THE PLAN. PRIOR TO SUBMITTING A BID ON THIS PROJECT, SUBSTITUTIONS MUST BE APPROVED BY THE MUNICIPAL ENGINEER.
- 5.BALLED AND BURLAPPED PLANTS SHALL BE DUG WITH FULL NATURAL BALLS OF EARTH, OF DIAMETER AND DEPTH TO INCLUDE MOST OF THE FIBROUS ROOTS. CONTAINER GROWN STOCK SHALL HAVE BEEN GROWN IN A CONTAINER LONG ENOUGH FOR THE ROOT SYSTEM TO HAVE DEVELOPED SUFFICIENTLY TO HOLD ITS SOIL TOGETHER FIRM AND WHOLE. NO PLANTS SHALL BE LOOSE IN THE CONTAINER.
- 6.MULCH FOR TREES, SHRUBS AND GROUND COVER SHALL BE DOUBLE-SHREDDED. A HARDWOOD MULCH, OWNER TO CORM COLOR: AGED AT LEAST ONE YEAR, CLEAR AND FREE OF WEEDS. PRE-EMERGENT WEED KILLER SHALL BE 'TREFLAN' OR APPROVED EQUAL. APPLY WEEK KILLER TO TOPSOIL, PRIOR TO MULCHING BED PLANTINGS. ALL SHRUBS TO BE PLANTED IN CONTINUOUS BEDS UNLESS OTHERWISE NOTED. ALL SHRUB BEDS TO RECEIVE 3" DEEP CONTINUOUS MULCH COVER. MULCH MAY NOT TOUCH THE TRUNKS OF TREES OR THE MAIN STEMS OF SHRUBS.
- 7.PREPARATION OF BACKFILL & PLANTING SOIL BEFORE MIXING, CLEAN TOPSOIL OF ACIDIC MARL, STICKS, ROOTS, PLANTS, TRASH, LARGE STONES, CLAY, LUMPS AND OTHER EXTRANEOUS MATERIALS HARMFUL OR TOXIC TO PLANT GROWTH, SOIL, (BACKFILL) FOR TREES, SHRUBS AND GROUNDCOVER SHALL BE MIXTURE BY VOLUME OF THE FOLLOWING MATERIALS IN QUANTITIES SPECIFIED; 1 PART PEAT MOSS TO 5 PARTS TOPSOIL
- 8.ALL PLANTS SHALL BE AT THE LOCATIONS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PLATING AT THE CORRECT GRADES, ALIGNMENT, AND TO THE INDICATED LAYOUT OF PLANTING BEDS.
- 9.THE CONTACTOR SHALL LAYOUT WITH IDENTIFIABLE STAKES INDIVIDUAL TREES AND SHRUB LOCATIONS AND AREAS FOR MULTIPLE PLANTING ALONG WITH THE ARRANGEMENTS AND OUTLINE OF PLANTING BEDS AS INDICATED ON THE DRAWINGS. FOR APPROVAL BY THE OWNER'S REPRESENTATIVE PRIOR TO EXCAVATION OF PLANTING PITS OR BEDS. AT LEAST THREE BUSINESS DAYS IS TO BE GIVEN TO PERMIT REVIEW AND APPROVAL OF PLANT LOCATIONS. DO NOT PROCEED WITH PLANTING WORK UNTIL APPROVAL IS GIVEN IN WRITING.
- 10. TOPSOIL SHALL BE INSTALLED BY THE CONTRACTOR AT A THICKNESS OF APPROXIMATELY FIVE (5) INCHES. CONTRACTOR IS RESPONSIBLE TO SUPPLY ALL TOPSOIL REQUIRED FOR BACKFILL MIXTURE.
- 11. THE PLANT ROOT BALL AND PREPARATION HOLE FOR BACKFILL MUST HAVE A WIDTH AT LEAST 1 FOOT GREATER THAN THE WIDTH OF THE ROOT BALL AND HAVE A DEPTH OF AT LEAST 6" MORE THAN THE HEIGHT OF THE ROOT BALL AS NOTED IN EACH TREE PLANTING DETAIL.

SUPPLEMENTAL WATERING NOTES

- 1. AN IRRIGATION SYSTEM WILL NOT BE PROVIDED ON SITE. AS WATERING IS A PRIMARY CONCERN FOR PLANT SURVIVAL THROUGHOUT THE ESTABLISHMENT & GUARANTEE PERIOD. FOR EACH CATEGORY OF PLANT; EVERGREEN OR CONIFEROUS TREES, DECIDUOUS SHADE TREES, DECIDUOUS ORNAMENTAL TREES, AND FOR SHRUBS THE RECOMMENDED WATERING REQUIREMENTS ARE AS FOLLOWS:
- 15 MINUTES / 1 TIME PER WEEK (\pm 1 GAL.)
- B. CONIFERS/EVERGREENS 30 MINUTES / 1 TIME PER WEEK (\pm 4-5 GAL.) C. ORNAMENTAL TREES 30 MINUTES / 1 TIME PER WEEK (\pm 4-5 GAL.)
- D. SHADE TREES 30 MINUTES / 1 TIME PER WEEK (\pm 4-5 GAL.)
- 2. WATERING REQUIREMENTS SHALL BE ADJUSTED AS NECESSARY DURING THE SEASONS; SPRING, HOT SUMMER MONTHS OR PERIODS OF DROUGHT AS NECESSARY TO ENSURE PLANT SURVIVAL FOR THE FULL DURATION OF THE GUARANTEE PERIOD.

CONSTRUCTION SEQUENCE

| IMPLEMENTATION OF COLL EDGGLON AND | |
|--|--------------------|
| IMPLEMENTATION OF SOIL EROSION AND SEDIMENT CONTROL MEASURES | 4 WEEKS |
| CLEAR CONCRETE SURFACE AND RIP-RAP | 1 WEEK |
| CONSTRUCT BOULDERS ROW AND RESTORE CHANNEL | 3 WEEKS |
| FINAL GRADING | 1 WEEK |
| ESTABLISH FINAL VEGETATIVE COVER | 1 WEEK |
| REMOVE SOIL EROSION MEASURES | 1 WEEK 11 WEEKS |

SOIL EROSION & SEDIMENT CONTROL COMPACTION NOTES

SOIL COMPACTION TESTING REQUIREMENTS

1. SUBGRADE SOILS PRIOR TO THE APPLICATION OF TOPSOIL (SEE PERMANENT SEEDING AND STABILIZATION NOTES FOR TOPSOIL REQUIREMENTS) SHALL BE FREE OF EXCESSIVE COMPACTION TO A DEPTH OF 6.0 INCHES TO ENHANCE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER.

2. AREAS OF THE SITE WHICH ARE SUBJECT TO COMPACTION TESTING AND/OR MITIGATION ARE GRAPHICALLY DENOTED ON THE CERTIFIED SOIL EROSION CONTROL PLAN.

3. <u>COMPACTION TESTING LOCATIONS</u> ARE DENOTED ON THE PLAN. A COPY OF THE PLAN OR PORTION OF THE PLAN SHALL BE USED TO MARK LOCATIONS OF TESTS, AND ATTACHED TO THE COMPACTION REMEDIATION FORM, AVAILABLE FROM THE LOCAL SOIL CONSERVATION DISTRICT. THIS FORM MUST BE FILLED OUT AND SUBMITTED PRIOR TO RECEIVING A CERTIFICATE OF COMPLIANCE FROM THE DISTRICT.

4. IN THE EVENT THAT TESTING INDICATES COMPACTION IN EXCESS OF THE MAXIMUM THRESHOLDS INDICATED FOR THE SIMPLIFIED TESTING METHODS (SEE DETAILS BELOW) THE CONTRACTOR/OWNER SHALL HAVE THE OPTION TO PERFORM EITHER (1) COMPACTION MITIGATION OVER THE ENTIRE MITIGATION AREA DENOTED ON THE PLAN (EXCLUDING EXEMPT AREAS), OR (2) PERFORM ADDITIONAL, MORE DETAILED TESTING TO ESTABLISH THE LIMITS OF EXCESSIVE COMPACTION WHEREUPON ONLY THE EXCESSIVELY COMPACTED AREAS WOULD REQUIRE COMPACTION MITIGATION. ADDITIONAL DETAILED TESTING SHALL BE PERFORMED BY A TRAINED, LICENSED PROFESSIONAL. FABRIC SECURED TO POST WITH METAL

COMPACTION TESTING METHODS

- A. PROBING WIRE TEST (SEE DETAIL)
- B. HAND-HELD PENETROMETER TEST (SEE DETAIL)
- C. TUBE BULK DENSITY TEST (LICENSED PROFESSIONAL ENGINEER REQUIRED D. NUCLEAR DENSITY TEST (LICENSED PROFESSIONAL ENGINEER REQUIRED)

NOTE: ADDITIONAL TESTING METHODS WHICH CONFORM TO ASTM STANDARDS AND SPECIFICATIONS, AND WHICH PRODUCE A DRY WEIGHT, SOIL BULK DENSITY MEASUREMENT MAY BE ALLOWED SUBJECT TO DISTRICT APPROVAL.

<u>SOIL COMPACTION TESTING IS NOT REQUIRED</u> IF/WHEN SUBSOIL COMPACTION REMEDIATION (SCARIFICATION/TILLAGE (6" MINIMUM DEPTH) OR SIMILAR) IS PROPOSED AS PART OF THE SEQUENCE OF CONSTRUCTION.

PROCEDURES FOR SOIL COMPACTION MITIGATION

PROCEDURES SHALL BE USED TO MITIGATE EXCESSIVE SOIL COMPACTION PRIOR TO PLACEMENT OF TOPSOIL AND ESTABLISHMENT OF PERMANENT VEGETATIVE COVER.

RESTORATION OF COMPACTED SOILS SHALL BE THROUGH DEEP SCARIFICATION/TILLAGE (6" MINIMUM DEPTH) WHERE THERE IS NO DANGER TO UNDERGROUND UTILITIES (CABLES, IRRIGATION SYSTEMS, ETC.). IN THE ALTERNATIVE, ANOTHER METHOD AS SPECIFIED BY A NEW JERSEY LICENSED PROFESSIONAL ENGINEER MAYBE SUBSTITUTED SUBJECT TO DISTRICT APPROVAL.

<u>SIMPLIFIED TESTING METHODS</u>

PROBING WIRE TEST- 15.5 GA STEEL WIRE (SURVEY) FLAG)

SOIL SHOULD BE MOIST BUT NOT SATURATED. DO NOT TEST WHEN SOIL IS EXCESSIVELY DRY OR SUBJECT TO FREEZING TEMPERATURES. SLOW, STEADY DOWNWARD PRESSURE USED WIRE MUST PENETRATE A TO ADVANCE THE WIRE. MINIMUM OF 6" WITHOUT 6" MIN. VISIBLE MARK MIRE MAY BE RE-INSERTED IF/WHEN ON WIRE AT DEPTH AN OBSTRUCTION (ROCK, ROOT,

HANDHELD SOIL PENETROMETER

DEBRIS) IS ENCOUNTERED


GAGE READING NOTE: SOIL SHOULD BE MOIST BUT 300 PSI OR NOT SATURATED. DO NOT TEST WHEN LESS AT 6" SOIL IS EXCESSIVELY DRY OR SUBJECT TO FREEZING TEMPERATURES. SLOW, STEADY DOWNWARD PRESSURE USED TO ADVANCE THE PROBE. PROBE MUST PENETRATE AT LEAST 6" WITH LESS THAN 300 PSI READING ON THE GAGE. 6" MIN. VISIBLE MARK PENETROMETER MAY BE ♦ ON WIRE AT DEPTH RE-INSERTED IF/WHEN AN OBSTRUCTION (ROCK, ROOT, DEBRIS) USE CORRECT SIZE


STAKE FOR STAKING-SAUCER AROUND TREES -REMOVE TOP 1/2 OF BURLAP ON BALL — COMPACTED PLANT MIXTURE



AND STAKING

N.T.S.





TREE PROTECTION TO DRIP LINE

- WATER SURFACE ROPE FORMS
ROPE FORMS
REINFORCEMENT AIDS IN
REMOVAL OR RELOCATION
OF BARRIER BY SERVING
AS A PICK-UP LINE FOR
WEIGHTS. ROPES AND
WEIGHTS ARE TO BE
ATTACHED TO END FLOATS
AND EVERY SECOND
FLOAT BETWEEN END
FLOATS. BRASS GROMMET -GROMMETS AT 2' C.C. TO CONNECT SECTIONS. TYPE AS TOP AND SAME BOTTOM FOLD WE'S -WEIGHT-BOTTOM -10 MIL. POLYETHYLENE PLASTIC SHEET OR SUITABLE ALTERNATE TO FIT EXISTING CONDITION AS APPROVED BY THE ENGINEER. FRONT VIEW FOLD TOP AND BOTTOM TO GET FOUR THICKNESSES OF MATERIAL. BODY OF WATER DISCHARGE POINT STREAM-DISCHARGE SHORE LINE OR DIKE POINT₇ APPLICATION

TYPICAL APPLICATION

POST

SECURELY FASTEN GEOTEXTILE TO WIRE FABRIC BY USE OF WIRE TIES OR HOG RINGS, THEN SANDWICH BETWEEN A 1" X 3" X 3"

4. SECURELY FASTEN ENDS OF INDIVIDUAL ROLLS OF GEOTEXTILE TO A COMMON POST BY WRAPPING EACH END OF THE GEOTEXTILE

AROUND A BATTEN TWICE AND ATTACHING THE BATTEN TO POST WITH SCREWS AT 6 INCH INTERVALS STARTING 3 INCHES FROM

- FLOATS

BATTEN AND THE POSTS PLACING SCREWS AT 6 INCH INTERVALS STARTING 3 INCHES FROM TOP.

HEAVY DUTY SILT FENCE


3. BURY BOTTOM 1 FOOT OF GEOTEXTILE AS PER SILT FENCE AND TAMP IN PLACE.

THE TOP. SPLICING OF INDIVIDUAL ROLLS SHALL NOT OCCUR AT LOW POINTS

2. BURY 4" X 4" FENCE POST 2'-0" BELOW GROUND.

5. BURY 6" OF WIRE FABRIC IN TIDAL AREAS.

_PLANT MIXTURE



1" - 2 1/2" DIA. CRUSHED STONE 6" THICK

-FILTER

 $^{\prime\prime}$

EXISTING GRADE

STABILIZED CONSTRUCTION ACCESS

FENCE POST-

(SPACING 8'- 0" C. TO C.)

SILT ACCUMULATION -

TRENCH, BURY BOTTOM

IN PLACE.

1'- 0" OF FABRIC, TAMP

FASTENERS AND WELDED WIRE MESH

BETWEEN FASTENER AND FABRIC.

SUBMARINE CABLE WET EXCAVATION OR BRIDGE STRUCTURE. (WET) GENERAL NOTES: PLACE SILT BARRIER TO PREVENT DRIFTING OF SILT CAUSED BY DISCHARGE OF STORM SEWERS DURING CONSTRUCTION, DREDGING OR FILLING OPERATIONS. EXACT PLACEMENT OF SILT BARRIER SHALL BE SO AS TO EFFECTIVELY CONTROL SILT DISPERSION UNDER THE CONDITIONS PRESENT ON A PARTICULAR PROJECT.

POST-PLUMB OR SLIGHTLY

- WIRE FABRIC

- 15 GAUGE WELDED

SQUARE OPENINGS

STEEL WIRE MESH, 4"

- 4" x 4" FENCE POST

GEOTEXTILE

(4'-0" WIDE)

OR METAL POST

GEOTEXTILE

SUITABLE ALTERNATE MAY BE FASTENED TO STAKES DRIVEN

INTO THE BOTTOM IN LIEU OF FLOATS AND WEIGHTS

FLOATING TURBIDITY BARRIER

N.T.S.

SURVEYED DRAWN DESIGNED CHECKER
BY BY BY BY **DESCRIPTION** NO. DATE



ENGINEERS - PLANNERS - SURVEYORS - SCIENTISTS 330 PHILLIPS AVENUE, SOUTH HACKENSACK, NJ 07606 TEL: (201) 641-0770 • FAX: (201) 641-1831 N.J. CERTIFICATE OF AUTHORIZATION No. 24GA27958000

KEVIN J. BOSWELL

TIP FOR SOIL TYPE

JOSEPH A. POMANTE

BANK STABILIZATION ALONG THE PECKMAN RIVER BLOCK 1703 LOT 54, 55, 56, 59, 60 SOIL EROSION AND SEDIMENT CONTROL DETAILS

MATERIALS MAY BE USED AS APPROVED

TOWNSHIP OF VERONA ESSEX COUNTY


NEW JERSEY SURVEYED BY DESIGNED BY SJ JOB NO. CHECKED BY FJR DRAWN BY RX AS NOTED VA-102

10/20/23

PROFESSIONAL ENGINEER N.J. LIC. 32943

PROFESSIONAL ENGINEER N.J. LIC. 43137

SHEET 11 OF 11 DRAWING NO. VA-102-SESC.DWG



BOSVELL EST 1924

A CENTURY OF EXCELLENCE

Engineered For Life

boswellengineering.com